

## ACCESSORIES

# ALUMINUM TERMINATION BAR

## PRODUCT INFORMATION

### DESCRIPTION:

The PLATINUM Termination Bar is expertly engineered to provide a seamless and professional finish for terminating single-ply membranes at parapet walls and other penetrations. Its flexible design allows it to conform to building irregularities, ensuring a clean and tidy termination. Crafted from **HIGH-QUALITY PREMIUM ALUMINUM ALLOY**, this termination bar offers superior strength and durability compared to plastic alternatives and is resistant to rust, maintaining its performance and appearance over time.

### FEATURES & BENEFITS:

- Extruded from lightweight premium Aluminum (6063-T5 grade alloy) with a smooth mill finish and no sharp edges for safety
- Features oval pre-drilled holes (5/16" x 3/8" or 8 x 10 mm) for easy installation
- Standard hole spacing of 6 inches (150 mm) on center for consistent mounting
- Measures 10 feet in length and 1 inch in width, providing ample coverage
- Thickness of 1/8 inch for durability and strength
- Includes a 1/8" lip sealant edge for a secure and reliable seal

### PACKAGING INFO:

All Platinum termination bars are available in 10-foot (3.05-meter) lengths. They are packaged in tubes containing 50 bars each, totaling 500 feet (152.5 meters) per package.

### INSTALLATION:

Termination bar is used for attaching and sealing flashing termination.

- 1 Surface Preparation:** Ensure that all substrates are free from dust, dirt, oil, water, and other contaminants. The wall areas above the Termination Bar must be properly waterproofed. Install the bar using suitable fasteners and in accordance with technical requirements.

- 2 Mastix Application:** Apply a continuous bead of Water Stop Mastix behind the top edge of the flashing to create a watertight seal.



- 3 Anchoring the Bar:** Secure the bar through the pre-punched holes, ensuring constant compression. Space the fasteners a maximum of 12 inches (304.8 mm) apart.
- 4 Bar Positioning:** Position the flat side of the bar towards the flashing to form a reservoir along the top edge for sealant application.
- 5 Spacing:** Maintain a 1/4-inch (6.3 mm) gap between each 10-foot (3 m) length of Platinum Termination Bar.
- 6 Vertical Installation:** Install the termination bar vertically where the base flashing ends.
- 7 Flashings Cleanup:** Trim any excess flashing material that extends above the bottom of the sealant reservoir channel.
- 8 Sealant Application:** Fill the reservoir channel with Sealer. For vertical installations or when working around wall obstructions, apply a continuous bead of Sealer around all sides of the Termination Bar.

### PRECAUTIONS

- Do not use the Termination Bar as a batten strip.
- If field cutting is necessary, remove any burrs from the bar ends and clean up any resulting shavings.
- Ensure the Termination Bar is installed directly onto the wall surface, not over existing sheet metal or flashings.
- Install the bar only on hard, smooth surfaces. Avoid installation on substrates where the seal is compromised, such as at mortar joints, or on wood and other porous materials.

There is no equal to **PLATINUM!**

Please note that PLATINUM products may be periodically updated & are subject to change without prior notice.  
For additional information, contact PLATINUM ROOFING PRODUCTS  
at 1-888-771-4686 or [info@platinumroofingproducts.ca](mailto:info@platinumroofingproducts.ca)